Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
65	KSRB-5.2-2: Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	52.00	6516.00	Rupees Six Thousand Five Hundred Sixteen Only
66	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. -Ground Floor	Cum	106.50	8425.00	Rupees Eight Thousand Four Hundred Twenty Five Only
67	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - First Floor	Cum	69.80	8487.00	Rupees Eight Thousand Four Hundred Eighty Seven Only
68	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - Second Floor	Cum	69.80	8549.00	Rupees Eight Thousand Five Hundred Forty Nine Only
69	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - Third Floor	Cum	69.80	8611.00	Rupees Eight Thousand Six Hundred Eleven Only
70	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - Terrace Floor	Cum	38.20	8673.00	Rupees Eight Thousand Six Hundred Seventy Three Only
71	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - Ground Floor	Sqm	120.30	1158.00	Rupees One Thousand One Hundred Fifty Eight Only
72	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - First Floor	Sqm	79.80	1164.00	Rupees One Thousand One Hundred Sixty Four Only
73	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - Second Floor	Sqm	79.80	1171.00	Rupees One Thousand One Hundred Seventy One Only

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
74	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - Third Floor	Sqm	79.80	1177.00	Rupees One Thousand One Hundred Seventy Seven Only
75	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Ground Floor	Sqm	879.60	303.00	Rupees Three Hundred Three Only
76	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - First Floor	Sqm	394.30	303.00	Rupees Three Hundred Three Only
77	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Second Floor	Sqm	394.30	303.00	Rupees Three Hundred Three Only
78	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Third Floor	Sqm	346.00	303.00	Rupees Three Hundred Three Only
	Above 125%	Sqm	48.30	379.83	Rupees Three Hundred Seventy Nine and Eighty Three Paise Only
79	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Terrace Floor	Sqm	292.00	303.00	Rupees Three Hundred Three Only
80	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Ground Floor	Sqm	1082.00	278.00	Rupees Two Hundred Seventy Eight Only
81	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - First Floor	Sqm	652.00	284.00	Rupees Two Hundred Eighty Four Only
82	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Second Floor	Sqm	652.00	291.00	Rupees Two Hundred Ninety One Only

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
83	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Third Floor	Sqm	652.00	297.00	Rupees Two Hundred Ninety Seven Only
84	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Terrace Floor	Sqm	76.00	297.00	Rupees Two Hundred Ninety Seven Only
85	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Ground floor	Sqm	1165.25	263.00	Rupees Two Hundred Sixty Three Only
	Above 125%	Sqm	1.75	291.74	Rupees Two Hundred Ninety One and Seventy Four Paise Only
86	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - First floor	Sqm	622.00	269.00	Rupees Two Hundred Sixty Nine Only
87	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Second floor	Sqm	622.00	276.00	Rupees Two Hundred Seventy Six Only
88	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Third floor	Sqm	622.00	282.00	Rupees Two Hundred Eighty Two Only
89	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Terrace floor	Sqm	29.55	288.00	Rupees Two Hundred Eighty Eight Only
	Above 125%	Sqm	22.17	316.57	Rupees Three Hundred Sixteen and Fifty Seven Paise Only
90	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Ground Floor	Sqm	138.00	195.00	Rupees One Hundred Ninety Five Only
91	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - First Floor	Sqm	113.75	201.00	Rupees Two Hundred One Only
	Above 125%	Sqm	23.25	244.57	Rupees Two Hundred Forty Four and Fifty Seven Paise Only
92	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Second Floor	Sqm	113.75	207.00	Rupees Two Hundred Seven Only

Contractor

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
	Above 125%	Sqm	23.25	250.77	Rupees Two Hundred Fifty and Seventy Seven Paise Only
93	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Third Floor	Sqm	113.75	214.00	Rupees Two Hundred Fourteen Only
	Above 125%	Sqm	23.25	256.98	Rupees Two Hundred Fifty Six and Ninety Eight Paise Only
94	Providing 20mm thick cement plaster in single coat with cement mortor 1:3, to Stone masonary & concrete Surface including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.- First Floor	Sqm	23.00	328.00	Rupees Three Hundred Twenty Eight Only
95	Providing 20mm thick cement plaster in single coat with cement mortor 1:3, to Stone masonary & concrete Surface including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.- Second Floor	Sqm	23.00	334.00	Rupees Three Hundred Thirty Four Only
96	Providing 20mm thick cement plaster in single coat with cement mortor 1:3, to Stone masonary & concrete Surface including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.- Third Floor	Sqm	23.00	340.00	Rupees Three Hundred Forty Only
97	KSRB 15.8.2 Providing and fixing plaster mesh 150mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment)	Rmtr	250.00	45.00	Rupees Forty Five Only
98	KSRB 15.8.2 Providing and fixing plaster mesh 200mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment)	Rmtr	300.00	53.00	Rupees Fifty Three Only
99	KSRB 15.9 Providing and fixing Corner beads 45x45mm size manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along exposed corners of walls, coloumns, lintels including cost of materials, labour for fixing complete . (length of mesh be measured for payment)	Rmtr	49.00	32.00	Rupees Thirty Two Only
100	Providing & applying Two coats of wall putty to inside plasterd walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of materials , cost of labour and scafolding etc complete as per specifications - For All Floors	Sqm	6199.00	70.00	Rupees Seventy Only
101	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Ground Floor	Sqm	1274.00	112.00	Rupees One Hundred Twelve Only

Contractor

Executive Engineer

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
102	viding & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - First Floor	Sqm	652.00	112.00	Rupees One Hundred Twelve Only
103	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Second Floor	Sqm	652.00	112.00	Rupees One Hundred Twelve Only
104	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Third Floor	Sqm	652.00	112.00	Rupees One Hundred Twelve Only
105	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Terrace Floor	Sqm	76.00	112.00	Rupees One Hundred Twelve Only
106	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications.-Ground Floor	Sqm	1167.00	117.00	Rupees One Hundred Seventeen Only
107	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications. -First Floor	Sqm	631.00	117.00	Rupees One Hundred Seventeen Only
108	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications.-Second Floor	Sqm	622.00	117.00	Rupees One Hundred Seventeen Only

Scanned with CamScanner

1	Description of Item	Unit	Qty	Rate in	
				Figures	Words
	2	3	4	5	6
109	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications. -Third Floor	Sqm	622.00	117.00	Rupees One Hundred Seventeen Only
110	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications. -Terrace Floor	Sqm	30.00	117.00	Rupees One Hundred Seventeen Only
	Above 125%	Sqm	22.00	111.73	Rupees One Hundred Eleven and Seventy Three Paise Only
111	Providing Textured paint of approved quality, colour and shade to wall surface after cleaning and rubbing the wall surface with wire brush of medium size emery stone to remove all the loosely adhering particles, the surface is then cleaned with water and ensured that it is in line and level. The textured material is then mixed with 40-50% of clean water until a homogeneous thick slurry is formed, the slurry is left for 5-10 min, to react completely with ingredients. The textured finish prepared as above is then applied to the wall surface with suitable roller/spray gun/putty/ blade / trowel to get the desired finish. The finished surface shall be applied with two coats of exterior paint of approved shade. The rate includes providing and removing scaffolding, all lead and lift and all other incidental charges etc., complete as per directions of the Engineer-in-charge of the work.	Sqm	300.00	439.00	Rupees Four Hundred Thirty Nine Only
112	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Ground Floor	Sqm	1043.00	191.00	Rupees One Hundred Ninety One Only
113	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - First Floor	Sqm	394.30	195.00	Rupees One Hundred Ninety Five Only
114	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Second Floor	Sqm	395.00	199.00	Rupees One Hundred Ninety Nine Only

Contractor

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
115	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Third Floor	Sqm	346.25	202.00	Rupees Two Hundred Two Only
	Above 125%	Sqm	48.75	223.46	Rupees Two Hundred Twenty Three and Forty Six Paise Only
116	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Terrace Floor	Sqm	292.00	206.00	Rupees Two Hundred Six Only
117	Providing Melamine polishing of approved shade including removing and refixing of doors shutters scraping with blade and rubbing with zero size sand paper and applying sealer coat by way of spraying with necessary compressor and applying patty after rubbing with steel wool including two coats of approved shade of Melamine polish etc., complete.	Sqm	23.75	895.00	Rupees Eight Hundred Ninety Five Only
	Above 125%	Sqm	6.25	1062.69	Rupees One Thousand Sixty Two and Sixty Nine Paise Only
118	KSRB 15-17.5 : Applying priming coat over new wood surface and / or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications.	Sqm	51.00	51.00	Rupees Fifty One Only
119	Providing and applying painting two coats on new wood surface and/ or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foregn matter, sand papering including cost of materials, labour complete as per specifications.	Sqm	51.00	104.00	Rupees One Hundred Four Only
120	KSRB 15-18.1 : Applying Red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.	Sqm	191.00	36.00	Rupees Thirty Six Only
121	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	371.60	102.00	Rupees One Hundred Two Only
122	Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, 25 mm thick, and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, mortar, labour, curing complete as per specifications. S	Sqm	23.20	3924.00	Rupees Three Thousand Nine Hundred Twenty Four Only
123	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Ground Floor	Sqm	47.50	4950.00	Rupees Four Thousand Nine Hundred Fifty Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
124	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - First Floor	Sqm	25.10	4952.00	Rupees Four Thousand Nine Hundred Fifty Two Only
125	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Second Floor	Sqm	25.10	4953.00	Rupees Four Thousand Nine Hundred Fifty Three Only
126	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Third Floor	Sqm	25.10	4955.00	Rupees Four Thousand Nine Hundred Fifty Five Only
127	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - Ground Floor	Sqm	47.00	3173.00	Rupees Three Thousand One Hundred Seventy Three Only
128	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - First Floor	Sqm	30.00	3175.00	Rupees Three Thousand One Hundred Seventy Five Only
129	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - Second Floor	Sqm	30.00	3177.00	Rupees Three Thousand One Hundred Seventy Seven Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
130	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - Third Floor	Sqm	30.00	3179.00	Rupees Three Thousand One Hundred Seventy Nine Only
131	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Ground Floor	Sqm	45.00	1390.00	Rupees One Thousand Three Hundred Ninety Only
132	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - First Floor	Sqm	22.50	1392.00	Rupees One Thousand Three Hundred Ninety Two Only
133	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Second Floor	Sqm	22.50	1394.00	Rupees One Thousand Three Hundred Ninety Four Only
134	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Third Floor	Sqm	22.50	1396.00	Rupees One Thousand Three Hundred Ninety Six Only
135	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete as per specification.	Sqm	65.10	4379.00	Rupees Four Thousand Three Hundred Seventy Nine Only
136	Providing full nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	Rmtr	50.00	295.00	Rupees Two Hundred Ninety Five Only
137	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	Rmtr	50.00	196.00	Rupees One Hundred Ninety Six Only

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in Figures	Rate in Words
1	2	3	4	5	6
138	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size 30x30cms - Ground Floor	Sqm	17.00	1460.00	Rupees One Thousand Four Hundred Sixty Only
139	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size 30x30cms - First Floor	Sqm	17.00	1462.00	Rupees One Thousand Four Hundred Sixty Two Only
140	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size 30x30cms - Second Floor	Sqm	11.63	1464.00	Rupees One Thousand Four Hundred Sixty Four Only
	Above 125%	Sqm	5.38	1505.89	Rupees One Thousand Five Hundred Five and Eighty Nine Paise Only
141	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size 30x30cms - Third Floor	Sqm	11.63	1466.00	Rupees One Thousand Four Hundred Sixty Six Only
	Above 125%	Sqm	5.38	1507.75	Rupees One Thousand Five Hundred Seven and Seventy Five Paise Only
142	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Ground Floor	Sqm	81.70	1842.00	Rupees One Thousand Eight Hundred Forty Two Only
143	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. First Floor	Sqm	81.70	1844.00	Rupees One Thousand Eight Hundred Forty Four Only
144	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.Second Floor	Sqm	81.70	1846.00	Rupees One Thousand Eight Hundred Forty Six Only
145	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.-Third Floor	Sqm	81.70	1848.00	Rupees One Thousand Eight Hundred Forty Eight Only

Contractor

Executive Engineer

Scanned with CamScanner